






# Please ensure you comply with the following instructions to optimise performance of the mixer:


- All pipework must be thoroughly flushed prior to installation
- For USA installation, please fix the USA NPT adapters on top of the pre-installed water connections
- Always first test the system with water pressure before closing the walls
- Optimal water pressure 3 BAR / temperature should not exceed 65°C/149°F
- Please read all installation instructions carefully

Failure to comply with manufacturers recommendations will void warranty

















## John Pawson by COCOON

## JP11.4

### **Operating conditions**

-Recommended flow temperature	≤65°C
-Maximum flow temperature momentary	≤90°C
-Minimum flow pressure	2 bar
-Maximum flow pressure	5 bar
-Recommended operating pressure	3 bar
-Test pressure	10 bar

#### Attention of the plumber

-The pipes have to be rinsed thoroughly before installation

-Avoid pressure differences between hot /cold water supply

-Use of pressure reducer when static pressure is higher than 5 bar to avoid damage the cartridge.

AERATORI IN DOTAZIONE / AERATORS INCLUDED

Aeratore montato / *Mounted aerator* 5.5 l/min / 1.2 gpm